ENGINEERING DEPARTMENT.

SHIMOGA DIVISION.

Notice is hereby given that sealed tenders will received at the Office of the Executive Engineer, Shimoga Division, up to 3rd August 1929, for filling in the breach and restoring Devabal Doddakere Regd. No. 189, Kumsi Sub-Taluk. An approximate estimate of quantities is given below. These quantities are not guranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for filling in the breach and restoring Devabal Doddakere Regd. No. 189, Kumsi Sub-Taluk" in default of which, tenders will be rejected.

4. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate of quantities for filling in breach and restoring Devabal Doddakere Reg. No. 189 in Kumsi Sub-Taluk, Shimoga District.

No.	Items of work	Quantity	
	I Bund R. L. 55·00		
1	Earthwork, excavating, carrying and watering and tamping...	C.yd.	4·872
2	Removing silt from the bed of breach	,,	52
3	Providing new rough stone revetment in front of breach ...	,,	207
4	Providing puddle wall in the centre	,,	90
5	Jungle clearing on the bund and preparing seat for it cutting steps in breach and removing roots, etc.	Lump	sum
6	Turfing the slopes	Sqr.	392·00
7	Preparing and fixing grade stones	No.	17
8	Do index stones	,,	17
9	Do Reg. No. and date stone ...	,,	1
10	Do B. M. stones	,,	2
11	Do gauge stone including cutting figures and painting.	,,	1
	II Sluice No. 1.		
1	Earthwork – Cutting open the bund and refilling including watering and tamping etc., complete.	C.yd.	27
2	Stone jelly concrete in surki mortar	C.ft.	81
3	Burnt brick in surki mortar	,,	165
4	Plastering with do	Sqr.	2·00
5	Burnt stone slabs 6" thick dressed and fixed	S.ft.	43
6	Cutting holes in orifice and guide slabs	No.	4
7	Preparing and fixing teakwood plug with iron rod and locking arrangements, etc., complete.	,,	1

No.	Items of work	Quantity	
	III Sluice No. 2.		
1	Earthwork—Cutting open the bund and refilling with watering and tamping, etc., complete.	C.yd.	26
2	Stone jelly concrete in surki mortar	C.ft.	81
3	Burnt brick in surki mortar	,,	176
4	Plastering with surki mortar	Sqr.	2·00
5	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	43
6	Cutting holes in orifice and guide slabs	No.	4
7	Preparing and fixing teakwood plug with iron rod and locking arrangements, etc., complete.	,,	1
	IV Waste Weir.		
1	Earthwork excavation for the weir and apron ...	C.yd.	67
2	Rough stone pitching	,,	71

M. A. SRINIVASACHARI,
Executive Engineer.

KOLAR DIVISION.

Notice dated 5th July 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 694 and 695, calling for tenders for Restoring Gollapalli, Byalakunte, Registered No. 597 of Chintamani Taluk, dated 11th July 1929.

The latest date for tender is 27th July 1929.

Notice dated 5th July 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 11th July 1929, Part VI, pages 707 and 708, calling for tenders for improving the Munsiff's Court at Chikballapur.

The latest date for tender is 27th July 1929.

Notice dated 5th July 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette* dated 11th July 1929, Part VI, pages 706 and 707, calling for tenders for Restoring Kondliganahalli, Kallukunte, Chintamani Taluk.

The latest date for tender is 27th July 1929.

Notice dated 5th July 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, dated 11th June 1929, Part VI, pages 704 and 705, calling for tenders for Restoring Krishnapur Kannegowdanakere of Malur Taluk.

The latest date for tender is 27th July 1929.

N. LAKSHMINARASIMIAH,
Executive Engineer.

MYSORE RAILWAYS, MYSORE.

Abstract Notification dated 20th July 1929.

Attention of the intending contractors is hereby invited to the Notice calling for tenders for "Widening of the Railway overbridge on the Yelwal Road at Mile 294—19-20 on Mysore-Nanjangud Section," published in pages 726-27 of Part VI of the *Mysore Gazette*, dated 18th July 1929. Tenders will be received any day up to 2 P.M. of 5th August 1929.

Y. K. RAMACHANDRA RAO,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 20th July 1929.

"The attention of the Public is invited to the notification published on page 727 of Part VI of *Mysore Gazette* dated 18th July 1929 calling for tenders for *closing the leaks in Madag tank bund*, Kadur Taluk. The last day for receiving tender is 1st August 1929 at 3 P.M."

L. A. H. WINCKLER,
Executive Engineer.